

MUNTONS PLC

CLIENT: MUNTONS



▶ THE PROJECT

At Ashcourt we are able to provide integrated solutions. Working on the Muntons's project is a fantastic example of this.

Our team of civil engineers, concrete managers along with our most trusted sub-contractors were able to work together as an effective team to make turn these complex plans into reality.

This project, the installation of 2no 20m silo bases and 1no 8m silo base, began with the excavation of the designated area.

The excavations works were carried out by Ashcourt's very own fleet and machinery including 8T 360, 14T 360, Merlo, 9T Dumpers and a 120 Roller.



▶ THE PROJECT

Team work was central to this project which progressed to having, 30mx2.5m high retaining wall's installed using steel columns and concrete panels to retain the bank where we reduced the ground ready for the installation of the bases.

Stone was brought in from our local quarry by our Ashcourt tipper wagons with formwork supplied by Leada acrow as well as having the support from Humberfix, our trusted steel fixers. The formwork for the project was then erected by Ashcourt's very own highly skilled joiners.

All of the concrete used for this project was supplied by Ashcourt and was poured using only Ashcourt pumps to ensure high end quality and consistency.



▶ DIVISIONS INVOLVED



Civil Engineering



Concrete



Aggregates



Construction

